Welcome RAJIV AWAS YOJNA (RAY)



In-Situ Development of Slums – Varanasi (UP) 1. Bajardiha, 2.Murgiya Tola, 3. Faruqui Nagar,

Nodal Agency:-STATE URBAN DEVELOPMENT AGENCY (SUDA), UP Navchetna Kendra, 10 Ashok Marg, Lucknow

Implementing Agency:-

CONSTRUCTION & DESIGN SERVICES, U.P. JAL NIGAM, VARANASI

INTRODUCTION


- Situated at 25°15' N 82° 15' E
- Population of Varanasi(2011)- 1597051
- No. of Slum(2007)- 228
- Total Slum Population(2007) 456000
- Proposed Slum in this DPR 3
- Covered population in these Slum 16908
- No. of House hold 2868
- Average house hold size 6
- Decadal Growth Rate 33%
- Total Area 79.79 Sq.Km.
- Water Supply:

Surface Water Source : No

Ground Water Source : Deep Tube Well

Sewerage System:

Area covered = 18%.




Slums - Issues

- 50 % houses in slums are pucca with brick wall, PCC flooring whereas others people live in Jhopris (Huts).
- Poor sanitation conditions due to clogged drains, collection of household waste water in open pits.
- Poor quality of water supply.
- Slums also lack toilet facility.
- No Pipe water Supply.

| | SC/ST | 42 |
|--------------------|----------|-----|
| Beneficiaries | OBC | 135 |
| | General | 12 |
| | Minority | 633 |
| | 822 | |
| Average H. H. Size | | 6 |

Social Composition of Slums Farrukhi Nagar, Bajardiha, Murgiya Tola, Varanasi



SOCIAL PROFILE

LIST OF SLUM FOR WHICH IN-SITU DEVELOPMENT IS PROPOSED

| <u>S No</u> | Slum Name | No. of Beneficiaries |
|-------------|---------------|----------------------|
| 1 | Bajardiha | 498 |
| 2 | Murgiya Tola | 217 |
| 3 | Faruqui Nagar | 107 |
| Total | | 822 |

Beneficiaries are identified by DUDA on the basis of their dwelling unit status and BPL status. The pucca house owners are not considered for redevelopment in this phase. A WHOLESLUM APPROACH HAS BEEN ADOPTED FOR PROVIDING INFRASTRUCTURE TO THE ENTIRE SLUM.

SLUM PROFILE: LIST OF SLUMS


SOCIAL SURVEY


| S.No. | Name of Slums | General | OBC | SC/ST | Minority | Pucca Houses | Total | No of houses to be taken up |
|-------|---------------|---------|-----|-------|----------|-----------------|-------|-----------------------------|
| 1 | Bajardiha | 12 | 101 | 15 | 370 | 1480 | 1978 | 498 |
| 2 | Murgiya Tola | 0 | 32 | 27 | 158 | 374 | 599 | 217 |
| 3 | Faruqui Nagar | 0 | 2 | 0 | 105 | 184 | 291 | 107 |
| | Total | 12 | 135 | 42 | 633 | 2038 | 2868 | 822 |

SOCIO ECONOMIC Livelihood Breakup (Occupational Survey)


| | Slum Name | Bajardiha | Murgiya Tola | Faruqui Nagar | Total |
|------|---------------------|-----------|--------------|---------------|-------|
| Main | Occupation | | | | |
| Sno | Description | | | | |
| 1 | Construction Labour | 115 | 58 | 75 | 248 |
| 2 | Driver | 3 | 1 | - | 4 |
| 3 | Bunker | 354 | 158 | 28 | 540 |
| 4 | Rickshaw Puller | 5 | - | 2 | 7 |
| 5 | Small Shopkeeper | 9 | - | - | 9 |
| 6 | Animal Husbandry | - | - | 2 | 2 |
| 7 | Tailor | 12 | - | - | 12 |
| | Total | 508 | 217 | 107 | 822 |


SLUM WISE SOCIO-ECONOMIC SURVEY






SLUM WISE LIVELIHOOD SURVEY







EXISTING CONDITION BAJARDIHA

BAJARDIHA

and a manufacture of the second

MURGIYA TOLA

FARUQUI NAGAR


COMMUNITY PARTICIPATION







SLUM LOCATION MAP

TO KAMACHHA (REVRI TALAB)





BAJARDIHA LAYOUT PLAN






MURGIYA TOLA LAYOUT PLAN






FARUQUI NAGAR LAYOUT PLAN




IN SITU HOUSING UNIT




Model – 1

Built-up area - 34.40 Sqm. Carper area - 26.30 Sqm. Model House Proposed Construction Cost- Rs. 3,74,890/-

IN SITU HOUSING UNIT



Model – 2 Built-up area - 31.99 Sqm. Carper area - 25.31 Sqm. Model House Proposed Construction Cost- Rs. 3,41,699/-



Preservation of Pond as Park

Financial Statement

| Particulars | Unit | Qty. | Amount Rs. In Lakhs | Central Shear | State Share | Benefici aries Share |
|---|------|----------|------------------------|------------------|----------------|----------------------------|
| Housing Cost | | | | | | |
| Model - 1 (778 Dus @ 374890/ -) | Each | 778 | 2916.64 | 1458.32 | 1458.32 | 0.00 |
| Model - 2 (44 Dus @341699 /-) | Each | 44 | 150.35 | 75.17 | 75.17 | 0.00 |
| Housing (822 DUs) | Each | 822 | 3066.99 | 1533.50 | 1533.50 | 0.00 |
| Infrastructure Cost | | | | | | |
| Interlocking concrete block pavement for 3.0 m ROW | Rmt. | 20771.00 | 326.94 | 163.47 | 163.47 | |
| Strom Water Drain (KC Drain) | Rmt. | 41543.00 | 167.42 | 83.71 | 83.71 | |
| Water Supply System | Job. | 3 | 305.21 | 152.61 | 152.61 | |
| Septic Tank with Sock Pit Tank | Each | 822 | 156.52 | 78.26 | 78.26 | |
| Street Lighting | Each | 80 | 33.42 | 16.71 | 16.71 | |
| Transit Housing for Temporary accommodation | Each | 206 | 30.90 | 15.45 | 15.45 | |
| Total Infrastructure | | | 1020.40 | 510.20 | 510.20 | |
| Total Housing + Utility Infrastructure | | | 4087.39 | 2043.70 | 2043.70 | 0.00 |
| Operation and Maintenance charges @ 4% | Job. | 1 | 163.50 | 81.75 | 81.75 | |
| Total Housing + Utility Infrastructure + Operation and maintenance | | | 4250.89 | 2125.44 | 2125.44 | |
| Total Other | Job. | 1 | 689.75 | 0.0 | 689.75 | |
| Grand Total | | | 4940.64 | 2125.44 | 2815.99 | 0.00 |

Percentage of Housing Cost : 75.04 % 24.96 %

Percentage of Infrastructure Cost :

IMPLEMENTATION PLAN

| Implementation Plan for RAY – Bajardiha, Murgiya Tola and Faruqui Nagar | | | | | | | | |
|---|---|----------------|-----------------|------------------|-----------------|----------------|-----------------|--|
| S.No. | Description of Activity | Year I | | | | Yea | Year II | |
| | | lst Quarter | lInd Quarter | IIIrd Quarter | IVth Quarter | Vth Quarter | VIth Quarter | |
| Activity 1 | Preparation of Tender Documents- General & Commercial Conditions | | | | | | | |
| Activity 2 | Tendering | | | | | | | |
| Activity 3 | Contractor Selection | | | | | | | |
| Activity 3.1 | Finalizing the conditions of contract | | | | | | | |
| Activity 3.2 | Negotiations of terms | | | | | | | |
| Activity 3.3 | Awarding of contract | | | | | | | |
| Activity 4 | Construction | | | | | | | |
| Activity 4.1 | Monitoring and Supervision | | | | | | | |
| Activity 4.2 | Scrutiny of Quantities | | | | | | | |
| Activity 4.3 | Quality Control | | | | | | | |
| Activity 5 | Assessment and final billing | | | | | | | |
| Activity 6 | Defect Liability | | | | | | | |
| Activity 7 | Closure of Accounts | | | | | | | |

Thanking You.....