



Detailed Project Report for In-situ Redevelopment of Vatrapalem Slum, Sullurpet



Presented by:

Municipal Council, Sullurpet


AP

13th, August, 2014

Sequence of Presentation

- About Sullurpet Town
- Slums in Sullurpet
- Evolution of Vatrapalem slum
- Profile of Vatrapalem Slum
- Inferences from household surveys
- Stages of Community participation
- Needs of slum dwellers identified during public consultations
- Strategy adopted for In-situ Redevelopment
- Proposed Layout

About Sullurpet Town




- Located in the southern part of Nellore district, along NH(5), connecting Vijayawada & Chennai
- Often termed as 'Gateway of Sriharikota,' as it provides access to SHAR), the only launch centre for Indian Space Research Organisation (ISRO) in India.
- Gram Panchayat until, 2012.
- Inception as Municipal Council was done on 21st January, 2012.
- Has potential to attract migrating population from surrounding rural areas due to increasing employment opportunities in the region and absence of other significant urban areas

Slums in Sullurpet


S No	Name of the Slum	Ward number	Population	Area (Ha)
1	Pandalagunta	6	96	0.21
2	Parasarathnam Colony	6	160	0.71
3	Isakamitta	6	504	2.96
4	Kollamitta	6	2,140	9.05
5	Kollamitta SC Colony	6	300	1.91
6	Rajiv nagar SC Colony	8	432	7.43
7	Kasareddy Palem	8	328	3.03
8	Bapuji colony	8	2,832	10.91
9	Sonia Gandi Nagar	8	432	2.27
10	Sulluru	12 & 13	1,992	3.82
11	Leprosy Colony	13	124	0.16
12	Indira nagar	12	648	0.68
13	Mahadevaiah nagar	4	340	3.00
14	Vatrapalem	3	2,081	7.5*
15	Mannarpoluru	2	1,214	10.61
16	Mannarpolur SC Colony	1	1,328	22.24
17	Pedda Girijina Colony	3	1,184	2.73
18	Chinna Girijana Colony	3	733	1.86
19	NTR Nagar	3	466	3.17
20	Pusala Colony	3	211	2.88
21	Mannarpoluru New colony	3	1,421	13.01
22	VMR Nagar	2	226	2.27
23	Sai nagar	4	884	17.63
24	Chinna Satram	4	156	0.82
25	Ganapathi Nagar	4 & 5	916	17.23

* Area based on Total Station Survey

Location of Vatrapalem Slum




Existing Slum Base Map




Profile of Vatrapalem slum

Total number of Households	587
Total population	2,081
Total area of slum	7.5 Ha
Number of pucca houses	23
Number of semi pucca houses	122
Number of kutcha houses	442
Number of commercial units	0
Community halls	0
Government buildings	0
Schools, primary & upper primary schools	0
Anganwadi centres	0
Parks	0
Urban health centers	0

Details of Exisitng Land use, Vatrapalem slum




Housing



Existing infrastructure facilities

Water supply

- Main utility Water Supply for the slum area is through the ELSR located in the central part of the slum, constructed by RWS&S department during 2012
- Total capacity of ELSR is 40 KL. Potable water is pumped on need basis to the ELSR from Minor Irrigation Tank, Konnembattu which is about 2.5 Km away.
- Current supply works out to 19.2 lpcd as against 135 lpcd
- Predominantly, households are dependent on public stand posts (PSPs)
- The total number of PSPs in the slum is 45
- Duration of water supply is for about 1hr (06:00 am to 07:00am).







Roads

- Main access to the slum is through an existing 6m wide kutcha road with about 9m RoW.
- Overall road width within the slum is consistently at about 6m.
- Despite of the availability of the width, the roads are non motorable due to mud in rainy seasons and the undulations in other seasons
- In interiors the roads are not maintained resulting growth of shrubs






Sanitation

- Predominantly, the households lack access to improved sanitation.
- Households with toilet are a meager 4%
- Open defecation is rampantly practiced in all surrounding areas.
- Open defecation areas are segregated on gender basis with an informal understanding among the households.
- 65% households lack bathrooms

 Remaining 35% households have temporary bathrooms which are open to sky







Storm Water Drainage

- Presently, the slum completely lacks drainage facility.
- Waste water generated by daily chores is let out into open plots or onto the roads.
- In some cases temporary pits are constructed by the households. After filling up of the pits, the grey water is manually drawn out and disposed into open areas.
- Due to the absence of drainage network, during the rainy season, the roads become completely non-motorable due to unsettling mud







Solid Waste Management

- Open dumping is practiced in all parts of the slum.
- Due to the availability of open space in the form of vacant plots, solid waste generated from the households in dumped in these open spaces.
- Vatrapalem slum is not integrated with the overall solid waste management practices of the town









Electrification

- The total number of electric poles provided for the entire slum is 20. Out of these 20 poles, 16 poles are provided with 4' tube lights for illumination. The overall illumination levels in the slum is very poor.
- Temporary wooden posts are erected by the slum dwellers to draw the electric connections to the households due to the unavailability of electric poles in the interior and peripheral areas which is hazardous.





Social Infrastructure

- During the preparation of layout, provisions for ST boys hostel is made by allotting land in the central part. However, the hostel is not developed and the land is vacant.
- In 2009, a primary school was constructed by Zilla Parishad, SPSR Nellore district, towards extreme western part without access road. Thus, it was closed within 3 months of inauguration. Presently, the structure is abandoned.

Stages of community participation

Stage 1: Reconnaissance visit



Meeting of TLF from all slums



Stage 2: Announcement of program



Stage 3: House numbering, demarcation of all slum area and vacant lands – Total Station Survey (TSS)







Stages of community participation.. Contd...

Stage 5: Data validation with representation from each household

	LLUMBER WERE THE	inte
FIT Trains	14030479993388	THE SHOW WANT
th beather	Train-Medical Rise	Space Name
S TOURS	a managaria	(care) ha Monte.
9-	1000	
E STATE OF	N team	and all the
3	-	circle or a payment.
Elitables.	-	100 p. st. 5.50
(Charles)	-	that a Francisco
There are a second	The Property lies	in calds
- TOTALI.	Tarantesis .	
Ship Hilliam C		Company of the State of the Sta
C TONALSE	N Same	en also
(3)	Trans-Spinot	100 Part (100 for for for
(2)	-	mercut.
Campaign	-	
(2)	- magnet	
(T) and the same	No har Holasti	on this tree
See A See Supplement		Tallia.
386 T-100		Mark to Supplied



Stage 6: Community Participation in Group Discussions



Stage 7: Displayed the list of beneficiaries on the wall of available public space & Consent for acceptance of Dwelling Units






Needs of slum dwellers identified during public consultations

S No	Issue	Action
1	Pucca houses	Addressed
2	Motorable pucca roads	Addressed
3	Drainage facility	Addressed
4	Street lighting	Addressed
5	Household water supply connections	Addressed
6	Individual toilets	Addressed
7	Community hall and library	Land provision made
8	Parks	Will be developed with ULB funds
9	Anganwadi centre & Primary school	To be tied up with Sarva Siksha Abhiyan
10	Public Distribution Supply facility (ration shop)	To be tied up with Revenue Department


Proposed Layout



Typical house Plan



Structural Details



Cost Estimates

S No	Component	Cost (Rupees in Lacs)
1	Housing	1,748.40
2	Infrastructure	571.68
3	O & M Cost	92.80
4	DPR Preparation, project management, Supervision & Quality Control	34.80
5	Labour cess	23.20
6	Social audit	11.60
7	VAT @5% (HOUSING)	87.42
8	VAT @5% (Infrastructure)	28.58
	Total	2,598.49

Financial Arrangements

						(Rs in lacs)						
	Scheme Component	Type	Qty. in Nos.	Rate (in Rs/Unit)	Proposed Project Cost	Appraised Project Cost	Central share	State Govt. Share	ULB Share	Beneficia ries Share		
				A.	HOUSING							
1	New in-situ Dwelling Units	GF	564	3.100	1748.40	1748.40	1269.00	262.26	0.00	217.14		
	Total Housing Cost S	Sub Total	(A) 90		1748.40	1748.40	1269.00	262.26	0.00	217.14		
			B.	INFRAST	RUCTURE							
1	Roads				239.83	138.76	102.22	20.81	15.72	0.00		
2	Water Supply				206.11	206.11	154.58	30.92	20.61	0.00		
3	Storm Water Drains				124.22	124.22	93.17	18.63	12.42	0.00		
4	Street Lighting				33.64	33.64	25.23	5.05	3.36	0.00		
5	Sewerage - Septic Tank	Nos	564	0.113	63.732	63.732	47.80	9.56	6.37	0.00		
6	Demolition of semi pucca structures	Nos	174		5.22	5.22	0.00	5.22	0.00	0.00		
	Sub Total (B)				672.75	571.68	423.00	90.19	58.49	0.00		
	Total (A	+B)			2421.15	2320.08	1692.00	352.45	58.49	217.14		
	Ratio of Housing to	Infrastru	Ratio of Housing to Infrastructure									

Financial Arrangements

	Scheme Component	Туре	Qty. in Nos.	Rate (in Rs/Unit)	Proposed Project Cost	Appraised Project Cost	Central share	State Govt. Share	ULB Share	Beneficia ries Share
1			C. O	peration	and Mainte	nance Cost				
	O&M Cost (up to 4%)		4%		96.85	92.80	69.60	23.20	0.00	0.00
	Sub Tota	ıl (C)			96.85	92.80	69.60	23.20	0.00	0.00
		Sub Total (A+B+C)			2518.00	2412.89	1761.60	375.65	58.49	217.14
				D.	Other Cost		•			'
1	DPR Preparation, project management, Supervision & Quality Control	1.50%		% of Total Cost	36.32	34.80	0.00	34.80	0.00	0.00
2	Labour cess	1.00%			24.21	23.20	0.00	23.20	0.00	0.00
3	Social audit	0.50%			12.11	11.60	0.00	11.60	0.00	0.00
4	VAT @5% (HOUSING)		0.16		87.42	87.42	0.00	87.42	0.00	0.00
5	VAT @5% (Infrastructure)		0.05		33.64	28.58	0.00	28.58	0.00	0.00
	Sub Total (D)				193.69	185.61	0.00	185.61	0.00	0.00
	Grand Total (A+B+C+D)				2,711.69	2,598.49	1,761.60	561.26	58.49	217.14

Thank You

SULLURPET MUNICIPALITY Appraised by HUDCO, New Delhi Dated 19.02.2014

									(R:	s in lacs)		
	Scheme	Туре	Qty. in	•	Propose		Central	State	ULB	Benefici		
	Component		Nos.	Rs/Unit)		ed	share	Govt.	Share	aries		
					Project	Project		Share		Share		
	1				Cost	Cost						
1		GF	564	3.100				262.26				
	Total Housin	•	ub Total		1748.40	1748.40	1269.00	262.26	0.00	217.14		
		A) 90										
				B. INFRA	STRUCT	URE						
	Roads											
	(i) Onsite	1										
	CC Roads	9.14metr	1383	0.07	90.43	90.43	67.82	13.56	9.04	0.00		
	VA/DA4 D	e	2222	0.04	400.0=	00.00	04.45	4.00		2.22		
1	WBM Roads	6.1metre	2820	0.01	129.27	28.20	21.15	4.23	2.82	0.00		
	(ii) Offsite	I I										
	CC Roads	9.14metr	200	0.10	20.13	20.13	13.25	3.02	3.86	0.00		
		e	O. I. T. (-1		200.00	400.70	400.00	00.04	45.70	0.00		
	W (0)	,	Sub Total		239.83	138.76	102.22	20.81	15.72	0.00		
	Water Supply											
	(i) Offsite	1			ī			1				
	Pumping Main & Pumpsets	metre	3500	0.031	109.96	109.96	82.47	16.49	11.00	0.00		
	(ii) Onsite											
2	Construction											
	of 250KL	KL	250	0.251	62.68	62.68	47.01	9.40	6.27	0.00		
	ELSR											
	Disrtibution	Rmt	2972	0.011	33.47	33.47	25.10	5.02	3.35	0.00		
	Pipe lines											
		,	Sub Total		206.11	206.11	154.58	30.92	20.61	0.00		

SULLURPET MUNICIPALITY Appraised by HUDCO, New Delhi Dated 19.02.2014

									(R	s in lacs)
	Scheme Component	Туре	Qty. in Nos.	Rate (in Rs/Unit)	Propose d Project Cost	ed	Central share	State Govt. Share	ULB Share	Benefici aries Share
	Storm Water									
	Drains (i) Onsite drain	Metre	6556.25	0.015	100.93	100.93	75.70	15.14	10.09	0.00
	<u> </u>									
3	(ii) Off site drain	Metre	179.65	0.044	7.99	7.99	5.99	1.20	0.80	0.00
	(iii) Culvert	Metre	390.2	0.039	15.3	15.3	11.48	2.30	1.53	0.00
			Sub Total		124.22	124.22	93.17	18.63	12.42	0.00
	Street Lighting									
	(i) HT/LT /									
4	supply line									
	works / street	No.s	105	0.32	33.64	33.64	25.23	5.05	3.36	0.00
	light pole and									
	transformers									
5	Severage									
	(i) Septic Tank	Nos	564	0.113	63.732	63.732	47.80	9.56	6.37	0.00
6	Demolition of	Nos	174		5.22	5.22	0.00	5.22	0.00	0.00
	semipucca									
		Sub	Total (B)		672.75	571.68	423.00	90.19	58.49	0.00
		To	otal (A+B)		2421.15	2320.08	1692.00	352.45	58.49	217.14
	R	atio of H	ousing to		74.87:25	75.00:25	75.00:25			
		Infra	structure		.13	.00	.00			

									(F	Rs in lacs)
	Scheme Component	Туре	Qty. in Nos.	Rate (in Rs/Unit)	Proposed Project Cost	Appraise d Project Cost	Central share	State Govt. Share	ULB Share	Beneficia ries Share
C Opera	ation and Mainten	ance Cost			•		•			
1	O&M Cost (up to 4%)		4%		96.85	92.80	69.60	23.20	0.00	0.00
		Sub	Total (C)		96.85	92.80	69.60	23.20	0.00	0.00
		Sub Tota	I (A+B+C)		2518.00	2412.89	1761.60	375.65	58.49	217.14
					D Other C	Cost				
1	DPR Preparation, project management, Supervision & Quality Control	1.50%		% of Total Cost	36.32	34.80	0.00	34.80	0.00	0.00
2	Labourcess	1.00%			24.21	23.20	0.00	23.20	0.00	0.00
3	Social audit	0.50%			12.11	11.60	0.00	11.60	0.00	0.00
4	VAT @5% (HOUSING)		0.16		87.42	87.42	0.00	87.42	0.00	0.00
5	VAT @5% (Infrastructure)		0.05		33.64	28.58	0.00	28.59	0.00	0.00
		Sub	Total (D)		193.69	185.61	0.00	185.61	0.00	0.00
	Gra	nd Total (A	\+B+C+D)		2711.69	2598.49	1761.60	561.26	58.49	217.14